



PAVEMENT REINSTATEMENT AS PER YSD502. DO NOT COST AS PART OF THIS CONTRACT ITEM

GENERAL NOTES

1. CONCRETE SHALL BE F'c 25 MPa AT 28 DAYS AND SHALL BE IN ACCORDANCE WITH THE CITY OF YARRA CONCRETE SPECIFICATION.
2. CONCRETE TO BE VIBRATED TO ENGINEER'S SATISFACTION. TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG (25KG) FOR EVERY CUBIC METRE OF CONCRETE.
3. KERB AND CHANNEL MACHINE MAY ONLY BE USED WITH THE APPROVAL OF THE ENGINEER.
4. EXPANSION JOINTS TO BE PROVIDED 1m EITHER SIDE OF VEHICLE CROSSINGS, 1m EITHER SIDE OF CENTRE OF TREES AND EVERY 20m MAX SPACING.
5. REFER MORE DETAILS ON STANDARD DRAWING YSD301.
6. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES UPON ARRIVAL TO SITE.
7. THE NEED FOR AN A.G. PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.

Yarra Standard: YSD302
Drawing Title:

CONCRETE KERB AND CHANNEL

Scale at A4 N.T.S

REV	DATE	DRAWN BY
A	29/11/07	HL
B	30/04/12	DKC
C	5/05/14	HL

