



GENERAL NOTES

1. CEMENT MORTAR WITHIN BLUESTONE JOINTS TO BE FINISHED FLUSH TO BLUESTONE SURFACE. BLUESTONE JOINTING TO BE MAXIMUM 15mm WIDE.
2. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES OF ARRIVAL ON SITE.
3. RE-INSTALEMENT OVER THE TRENCH SHALL EXTEND 150mm PAST THE FACE OF THE TRENCH AND EXTEND TO EITHER THE LIP OF THE CHANNEL OR TO THE BUILDING LINE AS DIRECTED BY COUNCIL'S REINSTATEMENT OFFICER.
4. TRAFFIC CONTROL MUST BE IN ACCORDANCE WITH AS 1742.3.
5. IN ACCORDANCE WITH THE ROAD MANAGEMENT ACT '04, THE RE-INSTALEMENT WORKS MUST BE MAINTAINED BY THE RELEVANT SERVICE AUTHORITY FOR A PERIOD OF 12 MONTHS. PRIOR TO THE 12 MONTH PERIOD, COUNCIL WILL NOTIFY THE RELEVANT SERVICE AUTHORITY OF ANY RECTIFICATION WORKS REQUIRED.
*N.B - A further 12 month maintenance period will then apply to the identified rectification works.

Yarra Standard: YSD1107
Drawing Title:
RE-INSTALEMENT WORKS
BLUESTONE VEHICLE CROSSING

Scale at A4 N.T.S

REV	DATE	DRAWN BY
A	15/10/96	CV
B	12/04/05	CV
C	04/12/12	SM

