


SECTION B-B

>166 DEGREES  
FOR DISABILITY ACCESS



SECTION A-A

**GENERAL NOTES**

1. CEMENT MORTAR WITHIN BLUESTONE JOINTS TO BE FINISHED FLUSH TO BLUESTONE SURFACE. BLUESTONE JOINTING TO BE MAX. 15mm WIDE.
2. ONLY SMOOTH PITCHERS TO BE USED IN THE PRAM CROSSING.
3. RE-INSTALL OR REPLACE ALL PERIPHERAL PAVING MATERIAL TO MATCH EXISTING.
4. CEMENT TREATED C.R TO BE LAID WITHIN 15 MINUTES OF ARRIVAL ON SITE.
5. REINSTATEMENT OF THE PRAM CROSSING BEYOND BLUESTONE CHANNEL TO BE AS PER FOOTPATH REINSTATEMENT STANDARD (YSD 1105).
6. TRAFFIC CONTROL MUST BE IN ACCORDANCE WITH AS 1742.3.
7. IN ACCORDANCE WITH THE ROAD MANAGEMENT ACT '04, THE RE-INSTALLMENT WORKS MUST BE MAINTAINED BY THE RELEVANT SERVICE AUTHORITY FOR A PERIOD OF 12 MONTHS. PRIOR TO THE 12 MONTH PERIOD, COUNCIL WILL NOTIFY THE RELEVANT SERVICE AUTHORITY OF ANY RECTIFICATION WORKS REQUIRED.

\*N.B - A further 12 month maintenance period will then apply to the identified rectification works.

**Yarra Standard: YSD1109**  
**Drawing Title:**

**RE-INSTALLMENT WORKS**  
**PITCHER PRAM CROSSING**

Scale at A4 N.T.S

REV	DATE	DRAWN BY
A	24/09/90	CV
B	12/04/05	DKC
S	04/12/12	SM

