



EXCAVATE EXISTING PAVEMENT TO SUBGRADE DEPTH. BACKFILL SHALL BE INDIGENOUS SOIL REMOVED FROM HOLE AND IS TO BE FREE FROM ANY FOREIGN MATERIAL. WHERE EXTRA BACKFILL SOIL IS REQUIRED, THE SOIL SHALL BE CONSISTENT WITH THE INDIGENOUS SOIL. THE FINISHED SURFACE SHOULD BE 100mm BELOW THE TOP OF NEW KERB. TOP WITH 100mm, 12-20mm PINE BARK MULCH.

**Yarra Standard: YSD320**  
**Drawing Title:**  
 Bluestone Tree Surrounds

Scale at A4 1: 20

REV	DATE	DRAWN BY
A	06/09/02	
B	30/04/12	DKC
C	04/10/13	OK

