



GENERAL NOTES

1. CHARCOAL COLOURED CONCRETE TO BE F_c 25MPa AT 28 DAYS.
2. CONCRETE TO BE POURED DIRECTLY OUT OF SUPPLY VEHICLE AND VIBRATED TO ENGINEER SATISFACTION.
3. THE 3% CEMENT TREATED C.R SHALL BE LAID WITHIN 15 MINUTES UPON ARRIVAL TO SITE. IT SHOULD BE 4% ABOVE OPTIMUM MOISTURES CONTENT.
4. PREPARATION OF SUBGRADE AS PER VICROADS SPECIFICATION SECTION 204 CLAUSE 204.15.
5. MINIMUM LONGITUDINAL GRADE OF LANE WAY TO BE 0.3%.
6. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATION OR SUPERVISING ENGINEER.

Yarra Standard:YSD506 Drawing Title:

TYPICAL LANE WAY : SPOON DRAIN
WITH ASPHALT FLANKS

Scale : N.T.S

REV	DATE	DRAWN BY
A	12/12/07	HL
B	30/04/12	DKC
C	04/10/13	OK

